
Introduce DevOps pipeline

Thang Nguyen











What's DevOps?

DevOps is a full lifecycle investment



DevOps is a team undertaking




DevOps enables better software development & delivery practices





DevOps accelerates the last mile of continuous delivery











- Learn the culture
 - Concept
 - Motivation
 - Factor Influencing
 - Barriers






Learn Server Administrator

- Linux OS
- Linux Commands
- File, permission, network

•



- Learn Webserver, Network,
 Protocol
 - TCP/IP
 - SSL, SSH, FTP...
 - Firewall, Load Balancer
 - Apache, Tomcat, IIS,...





- Learn Scripting & Programing language
 - IaC
 - PaC
 - Other languages






- Learn Git
 - Best of SCM





- Learn Container Architect
 - Docker
 - K8s
 - Rancher





- Learn Configuration Mgmt
 - Ansible
 - Chef
 - Puppet






- Learn Cloud IaC
 - Google Cloud
 - AWS








CI/CD



IaC Concepts









PaC Concepts

Ln 1, Col 11 Spaces: / UTF-B ERLF Groovy 🜲



Chosen pipeline



Demo Projects

- Simple Flask Python
- Jenkinfile



- Setup 4 Ubuntu servers
 - Virtual Box
 - Ubuntu 18.04



- Install Jenkins

```
wget -q -O - https://pkg.jenkins.io/debian-stable/jenkins.io.key | sudo apt-key add -
sudo sh -c 'echo deb http://pkg.jenkins.io/debian-stable binary/ > /etc/apt/sources.list.d/jenkins.list'
sudo apt update
sudo apt install jenkins
sudo systemctl start jenkins
```



Config Jenkins

- Initial Password: sudo cat /var/lib/jenkins/secrets/initialAdminPassword
- Install Plugins: Nexus Artifact Uploader, Github Plugin, Git Plugin, Publish Over SSH
- Config Plugins: Publish Over SSH (Config System)
- New Item > Pipeline Items
 - Config Pipeline from SCM
 - Poll SCM
- Change Jenkins build Step
- Test by Build Now

- Install Nexus

```
sudo apt-get update
sudo apt install openjdk-8-jre-headless
cd /opt
sudo wget https://download.sonatype.com/nexus/3/latest-unix.tar.gz
tar -zxvf latest-unix.tar.gz
sudo mv /opt/nexus-3.30.1-01 /opt/nexus
```

- Install Nexus

sudo adduser nexus

sudo visudo

Add new line: "nexus ALL=(ALL) NOPASSWD: ALL" and save

sudo chown -R nexus:nexus /opt/nexus

sudo chown -R nexus:nexus /opt/sonatype-work

sudo nano /opt/nexus/bin/nexus.rc

Uncomment the line and put run_as_user="nexus"

- Install Nexus

Change JVM heap size in /opt/nexus/bin/nexus.vmoptions

- -Xms1024m
- -Xmx1024m
- -XX:MaxDirectMemorySize=**1024m**
- -XX:LogFile=./sonatype-work/nexus3/log/jvm.log
- -XX:-OmitStackTraceInFastThrow
- -Djava.net.preferIPv4Stack=true
- -Dkaraf.home=.
- -Dkaraf.base=.
- -Dkaraf.etc=etc/karaf
- -Djava.util.logging.config.file=/etc/karaf/java.util.logging.properties
- -Dkaraf.data=./sonatype-work/nexus3
- -Dkaraf.log=./sonatype-work/nexus3/log
- -Djava.io.tmpdir=./sonatype-work/nexus3/tmp



- Install Nexus

Run Nexus as service:

sudo nano /etc/systemd/system/nexus.service and put content:

[Unit]

Description=nexus service

After=network.target

[Service]

Type=forking

LimitNOFILE=65536

ExecStart=/opt/nexus/bin/nexus start

ExecStop=/opt/nexus/bin/nexus stop

User=nexus

Restart=on-abort

[Install]

WantedBy=multi-user.target



Start Nexus

sudo systemctl start nexus sudo systemctl enable nexus sudo systemctl status nexus

Config Nexus

- Access via Web , port: 8081
- Initial password : cat /opt/nexus/sonatype-work/nexus3/admin.password
- Add repo: DeployPython (raw)

– Config Jenkins:

- Change Jenkins Upload Step using Syntax Generator

Install Ansible on Controller Node

```
sudo apt-add-repository ppa:ansible/ansible
sudo apt update
sudo apt install ansible
sudo nano /etc/ansible/hosts
Change file content:
[servers]
docker ansible_host=192.168.1.141
```

[all:vars]
ansible_python_interpreter=/usr/bin/python3



```
    Config Ansible – add ansibleadmin

sudo useradd ansibleadmin
sudo visudo and put line
"ansibleadmin ALL=(ALL) NOPASSWD: ALL"
sudo nano/etc/ssh/sshd_config change to PasswordAuthentication yes
(also add user ansibleadmin on Managed node)
- Generate keys:
ssh-keygen
ssh-copy-id <ip managed node>
Test by ssh without password.
```

Install docker on Managed Node

```
sudo apt update
sudo apt install apt-transport-https ca-certificates curl software-properties-common
curl -fsSL https://download.docker.com/linux/ubuntu/gpg | sudo apt-key add -
sudo add-apt-repository "deb [arch=amd64] https://download.docker.com/linux/ubuntu bionic stable"
sudo apt update
apt-cache policy docker-ce
sudo apt install docker-ce
sudo systemctl status docker
Add ansibleadmin to docker group: sudo usermod -aG docker ansibleadmin
sudo apt-get install python-docker
```

- Change Jenkinfile to add Deploy
- Write: DeployDocker.yaml on Ansible Controller Node
- Change Jenkin to sshUpload to control Ansible Controller Node to deploy on Managed Node
- Test by Build Now



Q&A

